

Downtown Square Sidewalks - City of Paris, Texas



The City of Paris, in conjunction with the Main Street Board and the Lamar County Chamber of Commerce, worked together to improve the conditions of the Downtown Square area in the City of Paris.

Improvements included, in Phase I: 23,489 SF of replacement sidewalk; 6,480 SF of textured asphalt sidewalks; 30 concrete curb ramps; 466 SF of asphalt street repair; 20 street lights; and 4 brick planters. Phase II improvements were for extensions on the NE, SE, and SW corners of the Square and included: 9,320 SF of replacement sidewalk; 1,069 SF of asphalt street repair; 1,084 SF of resurfacing existing sidewalk, and 12 street lights.

Services provided by Hayter Engineering are listed at right.

This project was unique because the contractor had to work around special events in the summer and fall, and maintain access to all businesses during construction. In addition, water and sewer service had to be maintained for the businesses and the contractor had to arrange the work to cause minimum inconvenience to the business owners.

This project was financed by the Texas Department of Transportation and it was completed in 2006.

CLIENT

City of Paris

CONTACT

John Godwin, City Manager
City of Paris
903-784-9202 (office)
jgodwin@paristexas.gov

CONSTRUCTION COST

\$741,292.79

SERVICES PROVIDED

Application for Financing
Cost Estimating
Design
Design Surveys
Bid & Award
Construction Review
Administration Review
TDLR Inspection
Warranty Review