

Hearne Street Extension First to Fourth Southwest Paris Economic Development Corporation Paris, Texas



This project provided drainage improvements and concrete paving for an extension of Hearne Street.

Improvements included 4,878 square yards of lime stabilized base course 8" thickness; 4,678 square yards of 8" reinforce concrete pavement including curb and gutter section, 29' back of curb to back of curb; 31 linear feet 15" RCP; 117 linear feet 13" x 22" RCP arch; and three combination inlets.

Services provided by Hayter Engineering are list at right.

This project was completed in 2004.

CLIENT

Paris Economic Development Corporation Paris, Texas

CONTACT

John Godwin, City Manager
City of Paris

903-784-9202 (office)

jgodwin@paristexas.gov

CONSTRUCTION COST

\$238,321.02

SERVICES PROVIDED

Cost Estimating

Design Surveys

Property-Boundary Surveys

Geotechnical Engineering

Design Plans & Specifications

Construction Bid & Award

Construction Review

Materials Testing

Warranty Review