

Heritage District - Sam Rayburn Drive & Main Street Bonham EDC & the City of Bonham, Texas



Streetscape Improvements included 50 decorative streetlights, 6,900 SF of stamped, colored concrete pavement, 1,465 LF of curb and gutter, 4,197 SF of 6" sidewalk or drive, 9,628 SF of 4" sidewalk, 15 curb ramps, and curb inlets and storm sewers. The entire project was constructed on TxDOT right-of-way which required close coordination with that agency. The design was complicated by the need to meet handicap accessibility requirements while matching existing grades and features.

Services provided by Hayter Engineering are listed at right.

The project was completed in 2001.

CLIENT

City of Bonham, TX & Bonham
Economic Development Corporation

CONTACT

Lance Capehart, Public Works Director
903-583-7555 (office)
903-583-0204 (cell)
lcapehart@cityofbonham.org

CONSTRUCTION COST

\$450,661.75

SERVICES PROVIDED

Paving & Sidewalk Design
Design Surveys
Cost Estimating
Bid & Award
Construction Review
One-Year Warranty Review