

Street System Improvements - City of Winnsboro, Texas



This project was preceded by a Street System Study completed in October of 2011 for the City of Winnsboro in which 99 streets were inventoried and classified.

A street plan was developed including recommended improvements for each street.

In the street improvements project two streets were completely reconstructed and 35 streets were overlaid with new asphalt. Seven of these streets had partial new curb and gutter (middle photo above) replacement and concrete valley gutter replacement.

Improvements included 46,124 SY of 2" asphalt wearing surface; 33,312 SY of 3" HMA; 676 LF of new concrete and gutter repair; and 2545 SY concrete valley gutter.

Services provided by Hayter Engineering are listed at right.

This project was completed 3 months ahead of schedule in 2012.

CLIENT

City of Winnsboro, Texas

CONTACTS

Jeff Howell, City Administrator, City of Winnsboro

Telephone: (903) 342-3654

E-mail: jhowell@winnsborotexas.com

Johnnie Lanier, Street Superintendent
(903) 342-0482

CONSTRUCTION COST

\$1,489,500.00

SERVICES PROVIDED:

Design Surveys

Design Plans & Specifications

Construction Bid & Award

Construction Review

Materials Testing

One-Year Warranty Review