

**Texas Department of Agriculture
San Antonio Drive & Colorado Street Paving
City of Avery, TX
Project ID: 7216020**



Hayter Engineering assisted the City of Avery to apply for a grant from the TDA Community Development Block Grant program. Colorado and San Antonio were in need of improvements (photos on the left above). Photos above are of Colorado Street (top row) and of San Antonio Drive (bottom row).

Colorado Street did not have existing base material once scarification was completed. San Antonio Street had more than 6" of existing road/base material and it was not advisable to disturb with the milling process. Low areas were leveled up and base failures were repaired in San Antonio and added asphalt wearing surface was added. Cement stabilization was added to Colorado Street to help the base material before adding asphalt. These improvements included: 8,452 SY of 2" HMA; 4,303 SY of cement stabilization; and 250 TN of asphalt level up course.

Services provided by Hayter Engineering are listed at right.

This project was completed in 2018.

CLIENT

City of Avery, TX

CONTACT

Alex Ackley, Mayor
Telephone: 903-684-3825
Email: cityofavery@yahoo.com

CONSTRUCTION COST

\$202,224.00

SERVICES PROVIDED

- Design Surveys
- Design Plans & Specifications
- Construction Bid & Award
- Construction Review
- Warranty Review